

AD-A087 328

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. GREEN TURTLE POND DAM (NJ00190), P--ETC(U)

FEB 80 J P TALERICA

DACW61-79-C-0011


NL

UNCLASSIFIED

1 OF 1  
AD-A  
JAN 1980



END  
DATE  
FILMED  
9-80  
DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

**LEVEL II**

PASSAIC RIVER BASIN  
BRANCH OF WANAUKE RIVER  
PASSAIC COUNTY  
NEW JERSEY

①

ADA 087328

# GREEN TURTLE POND DAM

NJ 00190

DTIC  
ELECTE  
JUL 24 1980

## PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.



APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.

THE QUALITY PRACTICALLY  
THE REPORTS TO DDC CONTAINED A  
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.

DDC FILE COPY

DEPARTMENT OF THE ARMY

Philadelphia District  
Corps of Engineers  
Philadelphia, Pennsylvania

FEBRUARY 1980

80 7 25 131

**NOTICE**


**THIS DOCUMENT HAS BEEN REPRODUCED  
FROM THE BEST COPY FURNISHED BY  
THE SPONSORING AGENCY. ALTHOUGH  
IT IS RECOGNIZED THAT CERTAIN POR-  
TIONS ARE ILLEGIBLE, IT IS BEING  
RELEASED IN THE INTEREST OF MAKING  
AVAILABLE AS MUCH INFORMATION AS  
POSSIBLE.**

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00190	2. GOVT ACCESSION NO. AD-A087328	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program. Green Turtle Pond Dam (NJ00190), Passaic River, Passaic County, NJ Basin Branch of		5. TYPE OF REPORT & PERIOD COVERED 9 FINAL rept.
7. AUTHOR(s) Wanaque River Passaic County, New Jersey. Phase I Inspection Report.		6. PERFORMING ORG. REPORT NUMBER 15 CONTRACT OR GRANT NUMBER(s) DACW61-79-C-0011
9. PERFORMING ORGANIZATION NAME AND ADDRESS Frederic R. Harris, Inc. 453 Amboy Ave. Woodbridge, N.J. 07095 Ed John P. Talor ca		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection Division of Water Resources P.O. Box CN029 Trenton, NJ 08625		12. REPORT DATE 11 Feb 1980
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106 (12) 81		13. NUMBER OF PAGES 66
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams Dam Safety Structural Analysis Visual inspection Green Turtle Pond Dam, NJ Seepage Piezometers Sediments National Dam Safety Program		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



DEPARTMENT OF THE ARMY  
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS  
CUSTOM HOUSE—2 D & CHESTNUT STREETS  
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO

NAPEN-N

82 JUL 1980

Honorable Brendan T. Byrne  
Governor of New Jersey  
Trenton, New Jersey 08621

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Green Turtle Pond Dam in Passaic County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Green Turtle Pond Dam, a high hazard potential structure, is judged to be in good overall condition and the spillway is considered adequate. To ensure adequacy of the structure, the following remedial actions, as a minimum, are recommended:

a. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months from the date of approval of the report.

b. The following remedial actions should be initiated within twelve months from the date of approval of this report:

(1) Observation wells or piezometers should be installed in the embankment to determine the location of the phreatic surface and the paths of the seepage observed.

(2) The flow of seepage should be monitored monthly to determine its volume and whether it presents a problem to the safety of the dam.

(3) Repair all cracked and spalled concrete in spillway and grouted riprap of downstream channel.

(4) All brush and trees should be removed from the downstream and upstream slopes. The embankment face should then be seeded to develop a growth of grass for surface erosion protection.

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.



NAPEN-N

Honorable Brendan T. Byrne

(5) Remove all vegetation and debris from the approach and discharge channels.

(6) Remove sediment from the low-level outlet pipe and the outlet stilling basin.

(7) Determine the exact location of the control for the low-level outlet and upgrade it so that the valve can be operated from the embankment crest. The controls should be operated at least once every six months.

(8) Investigate the embankment for animal burrows and fill in any burrow holes with impervious material.

c. Within twenty-four months from the date of approval of this report, the owner should consider providing additional low-level outlet facilities to decrease drawdown time.

d. Within one year from the date of approval of this report, the owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Roe of the Eleventh District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

2

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist.	Avail and/or special
A	23 CA

NAPEN-N

Honorable Brendan T. Byrne

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



1 Incl  
As stated

JAMES G. TON  
Colonel, Corps of Engineers  
District Engineer

Copies furnished:

Mr. Dirk C. Hofman, P.E., Deputy Director  
Division of Water Resources  
N.J. Dept. of Environmental Protection  
P.O. Box CN029  
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief  
Bureau of Flood Plain Regulation  
Division of Water Resources  
N.J. Dept. of Environmental Protection  
P.O. Box CN029  
Trenton, NJ 08625

GREEN TURTLE POND DAM (NJ00190)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 16 November 1979 by Harris - ECI Associates, Inc., under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Green Turtle Pond Dam, a high hazard potential structure, is judged to be in good overall condition and the spillway is considered adequate. To ensure adequacy of the structure, the following remedial actions, as a minimum, are recommended:

a. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months from the date of approval of the report.

b. The following remedial actions should be initiated within twelve months from the date of approval of this report:

(1) Observation wells or piezometers should be installed in the embankment to determine the location of the phreatic surface and the paths of the seepage observed.

(2) The flow of seepage should be monitored monthly to determine its volume and whether it presents a problem to the safety of the dam.

(3) Repair all cracked and spalled concrete in spillway and grouted riprap of downstream channel.

(4) All brush and trees should be removed from the downstream and upstream slopes. The embankment face should then be seeded to develop a growth of grass for surface erosion protection.

(5) Remove all vegetation and debris from the approach and discharge channels.

(6) Remove sediment from the low-level outlet pipe and the outlet stilling basin.

(7) Determine the exact location of the control for the low-level outlet and upgrade it so that the valve can be operated from the embankment crest. The controls should be operated at least once every six months.

(8) Investigate the embankment for animal burrows and fill in any burrow holes with impervious material.

c. Within twenty-four months from the date of approval of this report, the owner should consider providing additional low-level outlet facilities to decrease drawdown time.

d. Within one year from the date of approval of this report, the owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

APPROVED: \_\_\_\_\_

*James G. Ton*  
JAMES G. TON

Colonel, Corps of Engineers  
District Engineer

DATE: \_\_\_\_\_

*19 JUN 1980*

PASSAIC RIVER BASIN  
BRANCH OF WANAQUE RIVER, PASSAIC COUNTY  
NEW JERSEY

GREEN TURTLE POND DAM  
NJ00190

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED.

DEPARTMENT OF THE ARMY  
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS  
PHILADELPHIA, PENNSYLVANIA 19106

FEBRUARY, 1980

## PHASE I INSPECTION REPORT

### NATIONAL DAM SAFETY PROGRAM

Name of Dam: Green Turtle Pond, I.D. NJ 00190  
State Located: New Jersey  
County Located: Passaic County  
Stream: Branch of Wanaque River  
River Basin: Passaic River  
Date of Inspection: November 16, 1979

#### Assessment of General Conditions

Green Turtle Pond Dam is an earthfill dam containing a broad crested concrete weir spillway at the right end of the dam. The overall condition of the dam is good. There is no major sign of distress or instability in the embankment. There is a vertical crack in the left abutment. The downstream channel is well defined. The operation of the low-level outlet was not demonstrated since the control for the gate valve could not be located and the owner's representative was not present during the inspection. The hazard potential is rated as "high".

The spillway capacity of Green Turtle Pond Dam is considered adequate in view of the ability of the spillway to pass the SDF without overtopping the dam.

At present, the engineering data available is not sufficient to make a definitive statement on the stability of the dam, but based on the findings of the visual inspection, the preliminary assessment of static stability is that it is satisfactory. The following actions are recommended along with a timetable for their completion. All recommended actions should be conducted under the supervision of an Engineer who is experienced in the design, construction and inspection of dams.

1. Observation wells or piezometers should be installed in the embankment to determine the location of the phreatic surface and the paths of the seepage observed. This should be done within twelve months.
2. The flow of seepage should be monitored monthly to determine its volume and whether it presents a problem to the safety of the dam.
3. Repair all cracked and spalled concrete within twelve months.

4. All brush and trees should be removed from the downstream and upstream slopes to avoid problems which may develop from roots. The embankment face should then be seeded to develop a growth of grass for surface erosion protection. This program should be started within twelve months.
5. Remove all vegetation and debris from the approach and discharge channels within twelve months.
6. Remove sediment from low-level outlet pipe and outlet stilling basin within twelve months.
7. Determine exact location of control for low-level outlet and upgrade it so that the valve can be operated from the embankment crest within twelve months. The controls should be operated at least once every six months.
8. Investigate embankment for animal burrows and fill in any burrow holes with impervious material.
9. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months.

Furthermore, while of a less urgent nature, the following additional action is recommended and should be carried out within twenty-four months.

1. Consider providing additional low-level outlet facilities to decrease drawdown time.
2. The owner should develop within one (1) year after formal approval of the report, written operating procedures and a periodic maintenance plan to insure the safety of the dam.

  
John P. Talerico, P.E.  
Harris-ECI Associates



Photo taken on January 21, 1980

GREEN TURTLE POND DAM

View looking toward left abutment wall of spillway and embankment beyond wall.



## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the office of the Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

## TABLE OF CONTENTS

### ASSESSMENT OF GENERAL CONDITIONS

### OVERVIEW PHOTO

### PREFACE

### Page

SECTION 1	PROJECT INFORMATION .....	1
	1.1 General .....	1
	1.2 Description of Project .....	1
	1.3 Pertinent Data .....	4
SECTION 2	ENGINEERING DATA.....	6
	2.1 Design .....	6
	2.2 Construction.....	6
	2.3 Operation .....	6
	2.4 Evaluation.....	6
SECTION 3	VISUAL INSPECTION.....	7
	3.1 Findings .....	7
SECTION 4	OPERATION PROCEDURES.....	9
	4.1 Procedures .....	9
	4.2 Maintenance of Dam.....	9
	4.3 Maintenance of Operating Facilities.....	9
	4.4 Evaluation .....	9
SECTION 5	HYDRAULIC/HYDROLOGIC .....	10
	5.1 Evaluation of Features.....	10
SECTION 6	STRUCTURAL STABILITY .....	12
	6.1 Evaluation of Structural Stability.....	12
SECTION 7	ASSESSMENT/REMEDIAL MEASURES .....	14
	7.1 Dam Assessment .....	14
	7.2 Remedial Measures .....	14

TABLE OF CONTENTS CONTINUED

PLATES

No.

KEY MAP & VICINITY MAP.....	1 & 1A
GEOLOGIC MAP.....	2
DRAWINGS OF DAM.....	3-4

APPENDICES

APPENDIX A - CHECK LIST - VISUAL OBSERVATIONS CHECK LIST - ENGINEERING, CONSTRUCTION, MAINTENANCE DATA.....	1-14
APPENDIX B - PHOTOGRAPHS	
APPENDIX C - SUMMARY OF ENGINEERING DATA.....	1
APPENDIX D - HYDROLOGIC COMPUTATIONS.....	1-13

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
GREEN TURTLE POND DAM, I.D. NJ 00190

S E C T I O N 1

1. PROJECT INFORMATION

1.1 General

a. Authority

The National Dam Inspection Act (Public Law 92-367, 1972) provides for the National Inventory and Inspection Program by the U.S. Army Corps of Engineers. This inspection was made in accordance with this authority under Contract C-FPM No. 35 with the State of New Jersey who, in turn, is contracted to the Philadelphia District of the Corps of Engineers, and was carried out by the engineering firm of Harris-ECI Associates, Woodbridge, New Jersey.

b. Purpose of Inspection

The visual inspection of Green Turtle Pond Dam was made on November 16, 1979. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.

c. Scope of Report

The report summarizes available pertinent data relating to the project; presents a summary of visual observations made during the field inspection; presents an evaluation of hydrologic and hydraulic conditions at the site; presents an evaluation as to the structural adequacy of the various project features; and assesses the general condition of the dam with respect to safety.

1.2 Description of Project

a. Description of Dam and Appurtenances

Green Turtle Pond Dam is an earthfill dam approximately 305-ft. long and 35-ft. high with a compacted clay fill core wall. There is a 30-ft. wide broad crested concrete weir spillway at the right end of the dam. The crest of the spillway is 4.0 ft. below the top of the dam. The embankment crest has a

width of 20 feet with an upstream slope of 5H:IV and a downstream slope of 4H:IV. Riprap protection has been placed on the upstream face of the embankment.

The low-level outlet consists of a 18-inch cast iron pipe through the dam approximately 400 feet left of the spillway. The flow through the pipe is controlled by a manually operated gate valve located in the upstream side of the embankment. The inlet end of the pipe is located at the upstream toe of the slope. The outlet discharges into a stilling pool at the end of the spillway channel. From the pool the flow continues in a southerly direction approximately 750 feet to a 6-foot diameter R.C.P. passing under Awosting Road.

There are no records of any borings and/or test pits taken for this dam.

A generalized description of soil conditions is contained in Report No. 3, Passaic County, Engineering Soil Survey of New Jersey, by Rutgers University. The report describes the dam site as Gneiss bedrock, erratically covered with a variable but thin, mantle of unconsolidated glacial materials. The bedrock is further described by Geologic Overlay Sheet 23 as Hornblende Granite and Gneiss.

b. Location

Green Turtle Pond Dam is located on a branch of the Wanaque River in the Township of West Milford, Passaic County, New Jersey. It is accessible by way of Awosting Road.

c. Size Classification

According to the "Recommended Guidelines for Safety Inspection of Dams" by the U.S. Department of the Army, Office of the Chief of Engineers, the dam is classified in the dam size category as being "small", since its storage volume of 368 acre-feet is less than 1,000 acre-feet. The dam is also classified as small because its height of 35 feet is less than 40 feet. The overall size classification of Green Turtle Pond Dam is small.

d. Hazard Classification

A hazard potential classification of "high" has been assigned to the dam on the basis that a hypothetical failure would result in excessive damage to road immediately downstream of the dam, because the road is heavily traveled and there are several habitable buildings immediately downstream. The possibility exists of the loss of more than a few lives in the event of dam failure.

e. Ownership

Green Turtle Pond Dam is owned by:

State of N.J. Green Acres  
Department of Conservation  
Trenton, NJ 08625

Attention: Mr. Curt Eubert  
Director, Green Acres

f. Purpose

Green Turtle Pond Dam is presently used for recreational purposes only.

g. Design and Construction History

A permit to construct Green Turtle Pond Dam was issued in 1957 and construction was completed in 1958. A summary of the construction history, from initial application to final acceptance of the dam, is available on microfilm at the N.J. Department of Environmental Protection.

h. Normal Operating Procedures

The discharge from the lake is unregulated and is allowed to naturally balance the inflow into the lake. The low-level outlet is used to lower the lake level by a manually operated gate valve which could not be located at the time of the inspection. Also, the owner's representative was not present to operate the valve at the time of the inspection.

1.3 Pertinent Data

a. Drainage Area 0.5 sq. mi.

b. Discharge at Dam Site

Ungated spillway capacity at elevation of top of dam: 744 cfs (elev. 580, NGVD)

Total spillway capacity at maximum pool elevation (SDF): 679 cfs (elev. 579.76 NGVD)

c. Elevation (Feet above NGVD)

Top of dam: 580

Maximum pool design surcharge (SDF): 579.76

Recreation pool: 576.3

Spillway crest: 576.0

Streambed at centerline of dam: 545 (estimated)

Maximum tailwater: 546.5 (estimated)

d. Reservoir

Length of maximum pool: 2,500 ft. (estimated)

Length of recreation pool: 2,400 ft. (estimated)

e. Storage (acre-feet)

Spillway crest: 251

Top of dam: 386

Maximum pool (SDF): 368

f. Reservoir Surface (acres)

Top of dam: 39

Maximum pool (SDF) 33 (estimated)

Recreation pool: N/A

Spillway crest: 28 (estimated)

g. Dam

Type:	Earth fill with broad crest weir
Length:	305 ft. (effective)
Height:	35 ft.
Top width:	20 ft.
Side slopes - Upstream:	5H:1V
- Downstream:	4H:1V
Zoning:	Unknown
Impervious core:	Clay core, 580-ft. long
Cutoff:	None
Grout curtain:	None

h. Diversion and Regulating Tunnel

N/A.

i. Spillway

Type:	Broad crest weir with notch at center
Length of weir:	30 ft.
Crest elevation:	576
Gates:	None
U/S Channel:	Green Turtle Pond
D/S Channel:	Side channel discharge to Natural channel

j. Regulating Outlets

Low level outlet:	18-inch C.I.P.
Controls:	Manually operated outlet gate
Emergency gate:	None
Outlet:	546 (NVGD) estimated



## SECTION 2

### 2. ENGINEERING DATA

#### 2.1 Design

Drawings for the original construction of Green Turtle Pond Dam in 1957 are on microfilm and are available at the Trenton offices of the N.J. Department of Environmental Protection (NJ-DEP). In addition, a gradation analysis of the soil used to build the dam are on file at the NJ-DEP. Also, recommendations for soil borings and/or test pits are available, but there is no record of the logs.

#### 2.2 Construction

Data is not available concerning the as-built construction of the dam. Some data exists on the proposed construction methods, borrow sources, and other data pertinent to the construction of the dam at the NJ-DEP.

#### 2.3 Operation

Formal operation records are not kept for the dam and reservoir. The lake is allowed to operate naturally without regulation.

#### 2.4 Evaluation

##### a. Availability

The availability of engineering data is good. The stated drawings, computations and some correspondence concerning the construction are available from the NJ-DEP.

##### b. Adequacy

The engineering data available, together with that obtained in the field, were adequate to perform hydrologic and hydraulic computations. The data was insufficient to perform a stability analysis, but preliminary evaluation could be made based on visual observations.

##### c. Validity

Information contained in the drawings and checked by limited field measurements appears to be valid.

## SECTION 3

### 3. VISUAL INSPECTION

#### 3.1 Findings

##### a. General

The visual inspection of Green Turtle Pond Dam revealed the dam and spillway to be in good condition, but in need of minor repairs and maintenance. The lake level was above the crest of the spillway at the time of the inspection.

##### b. Dam

The earth embankment appears to be sound. No surface cracking on the embankment or at the toe was noted. No erosion of the embankment was observed. No misalignment of the embankment in the horizontal or vertical plane was evident. Numerous trees, small to large size are growing on both embankment sides. A few trees were uprooted leaving small cavities on the downstream slope. Minor seepage was occurring at two locations. One seepage location was 5 feet right of the low-level outlet drain and the other was approximately 100 feet downstream of the spillway, 5 feet left of the channel. No evidence of burrowing by animals was discovered; however, at the time of the inspection, the embankment was covered with leaves, therefore the possibility does exist that there may be burrow holes in the embankment.

##### c. Appurtenant Structures

###### 1. Spillways

A concrete spillway exists on the right side of the embankment. The spillway is in good condition and is notched (3'-6" wide x 3" high) at the center. No seepage or leakage was noticed at the spillway. Minor spalling and two very small surface cracks were observed at the right abutment of the spillway. A vertical crack extends from the top of the left abutment to the apron at the spillway. Horizontal and vertical alignment of the crest are good. A long concrete apron serves as the approach channel. Fallen trees, vegetation and silt clutter this approach channel.

###### 2. Outlet Works

An 18-inch diameter cast iron pipe was observed exiting at the downstream side of the embankment at the channel pool. This low level outlet pipe was three-quarters full of sediment. The surface of the stilling basin was covered with sediment. No low level outlet control was found on the upstream side of embankment as shown on the embankment plans or in the vicinity of the embankment.

d. Reservoir Area

Earth slopes and rock outcropping encompass the reservoir. The earth slopes are moderate and stable while the rock slopes are steep and firm. There are no structures situated on the reservoir rim.

e. Downstream Channel

The bottom of the downstream channel is grouted riprap and is in good condition. There are some cracks in the grout. Some vegetation, fallen trees and debris are in the channel. The channel flow runs into a pool that is located approximately 230 feet from the spillway. From the pool, the flow continues through a 6-foot diameter reinforced concrete pipe under Awosting Road, which is located approximately 1,000 feet from the spillway. The discharge then passes under Greenwood Lake Turnpike, which is located approximately 250 feet downstream from Awosting Road.

## SECTION 4

### 4. OPERATIONAL PROCEDURES

#### 4.1 Procedures

Green Turtle Pond Dam is used to impound water for recreational activities. The level of the lake is maintained through the unregulated flow over the spillway and the lake is not lowered on a regular basis.

#### 4.2 Maintenance of the Dam

There is no regular inspection and maintenance program for the dam and appurtenant structures. The State of New Jersey Green Acres, Department of Conservation is responsible for the maintenance of the dam.

#### 4.3 Maintenance of Operating Facilities

The low-level operating facilities consist of the one manually operated 18 inch gate valve. At the time of inspection, operation of the valve was not demonstrated because the gate valve could not be found and the owner's representative was not present.

#### 4.4 Evaluation

The present operational and maintenance procedures are fair with the dam and spillway being maintained in a serviceable condition.

## SECTION 5

### 5. HYDRAULIC/HYDROLOGIC

#### 5.1 Evaluation of Features

##### a. Design

The drainage area above Green Turtle Pond Dam is approximately 0.50 square miles. A drainage map of the water shed of the dam site is presented on Plate 1, Appendix D.

The topography within the basin is flat. Elevations range from approximately 840 feet above NGVD at the North end of the watershed to about 580 feet at the dam site. Land use patterns within the watershed are mostly woodland with concentrated residential development around the lake area.

The evaluation of the hydraulic and hydrologic features of the dam and lake was based on criteria set forth in the Corps Guidelines and additional guidance provided by the Philadelphia District, Corps of Engineers. The Spillway Design Flood (SDF) for the dam is equal to the 1/2 PMF.

The Probable Maximum Flood (PMF) was calculated from the probable maximum precipitation using Hydrometeorological Report No. 33 with standard reduction factors. Due to the small drainage area, the SCS triangular hydrograph transformed to a curvilinear hydrograph was adopted for developing the unit hydrograph, with the aid of the HEC-1-DM Flood Hydrograph Computer Program.

Initial and infiltration loss rates, were applied to the Probable Maximum Precipitation to obtain rainfall excesses. The rainfall excesses were applied to the unit hydrograph to obtain the PMF and various ratios of PMF utilizing program HEC-1-DR.

The SDF outflow calculated for the dam is 679 cfs. This value is derived from half PMF, assuming that the lake was originally at the spillway crest elevation. The half PMF was routed through the dam and it was found the dam would not overtop. There would be approximately half foot of freeboard remaining. Based on the routing, it can be concluded that Green Turtle Pond Dam is adequate.

The stage-outflow relation for the spillway was determined from the geometry of the spillway and dam, utilizing HEC-1-DB program.

The reservoir stage-storage capacity relationship was computed directly by the conic method, utilizing the HEC-1-DB program. The reservoir surface areas at various elevations were measured by planimeter from USGS Quadrangle topographic map. Reservoir storage capacity included surcharge levels exceeding the top of the dam

and the spillway rating curve was based on the assumption that the dam remains intact during routing.

Breach analysis is not required since the spillway capacity is adequate.

Drawdown calculations indicate that to empty the lake to an elevation of 552 NGVD through the one low-level sluice would take 4 days, excluding inflow. This is considered to be an excessive drawdown period, and provision of additional outlets should be considered.

b. Experience Data

No records of reservoir stage or spillway discharge are maintained for this site.

c. Visual Observation

The downstream channel is well defined. Grouted riprap is on the bottom. The slopes of the channel are shallow to moderate. There are three houses on the left bank of the downstream channel, beyond Greenwood Lake Turnpike, located approximately 1,300 feet from the spillway.

Earth slopes and rock outcropping encircle the reservoir. The earth slopes are moderate and stable while the rock slopes are steep and firm. The drainage area is wooded and moderately flat sloped.

d. Overtopping Potential

As indicated in Section 5.1.a, the spillway capacity of Green Turtle Pond Dam is considered adequate to pass the SDF with no overtopping potential.

## SECTION 6

### 6. STRUCTURAL STABILITY

#### 6.1 Evaluation of Structural Stability

##### a. Visual Observations

There are no major signs of distress in the embankment of the Green Turtle Pond Dam. Trees growing on both embankment sides could pose a threat to stability. A few small cavities created by uprooted trees were observed. Seepage was occurring at two locations. One seepage location was 5 feet right of the low level outlet and the other was about 100 feet downstream of the spillway, 5 feet left of the channel. The seepage has not been monitored and no information was uncovered concerning their duration or flow rates. No evidence of burrowing animals was observed; however, the embankment was covered with leaves and therefore the possibility does exist that there may be burrow holes in the embankment. The spillway is in good condition but does show minor spalling, and cracking.

##### b. Design and Construction Data

No design computations relating to stability were uncovered during the report preparation phase. No embankment or foundation soil parameters are available for carrying out a conventional stability analysis on the embankment. No construction data or specifications relating to the degree of embankment compaction are available for use in the stability analysis.

##### c. Operating Records

No operating records are available relating to the stability of the dam. The dam and spillway have served satisfactorily since its construction in 1958.

##### d. Post-Construction Changes

None on record.

##### e. Static Stability

A static stability analysis was not performed for Green Turtle Pond Dam because the lack of data on which to base assumptions of material properties and embankment cross-sections might produce misleading results, but based on the findings of the visual inspection, the preliminary assessment of static stability is that it is satisfactory.

f. Seismic Stability

Green Turtle Pond Dam is located in Seismic Zone 1, as defined in Recommended Guidelines for Safety Inspection of Dams, prepared by the Corps of Engineers. In general, projects located in Seismic Zones 0, 1 and 2 may be assumed to present no hazard from earthquake, provided the static stability condition are satisfactory and conventional safety margins exist. Since static stability safety factors have not been confirmed, it cannot be stated that seismic stability is satisfactory.



## SECTION 7

### 7. ASSESSMENT/REMEDIAL MEASURES

#### 7.1 Dam Assessment

##### a. Safety

The dam has been inspected visually and a review has been made of the available engineering data. This assessment is subject to the limitations inherent in the visual inspection procedures stipulated by the Corps of Engineers for a Phase I report.

The adequacy of Green Turtle Pond Dam is not in question because the dam does have adequate spillway capacity to pass half of the PMF, which is the SDF for the dam, without overtopping.

No definitive statement pertaining to the safety of the embankment can be made without acquisition of embankment material engineering properties, but based on the findings of the visual inspection, the preliminary assessment of static stability is that it is satisfactory.

##### b. Adequacy of Information

The information uncovered was adequate to perform hydrologic and hydraulic computations. The data was insufficient to perform even an approximate computation of the stability of the dam. A preliminary assessment of the dam could be made by visual observation only.

##### c. Urgency

Observation wells or piezometers should be installed in the embankment to determine the location of the phreatic surface and the paths of the seepage observed. This should be done within twelve months.

The flow of seepage should be monitored monthly to determine its volume and whether it presents a problem to the safety of the dam.

The existing dam plans and drawings should be annotated and updated to form a coherent as-built set within twelve months.

#### 7.2 Remedial Measures

##### a. Alternatives for Increasing Spillway Capacity

1. Alternatives for increasing spillway capacity are not necessary as it is adequate to handle the SDF.

b. Recommendations

1. Repair all cracked and spalled concrete within twelve months.
2. All brush and trees should be removed from the downstream and upstream slopes to avoid problems which may develop from roots. The embankment face should then be seeded to develop a growth of grass for surface erosion protection. This program should be started within twelve months.
3. Remove all vegetation and debris from the approach and discharge channels within twelve months.
4. Remove sediment from low level outlet pipe and outlet stilling basin within twelve months.
5. Determine exact location of controls for low level outlet and upgrade it so that the valve can be operated from the embankment crest, within twelve months. The controls should be operated at least once every six months.
6. Investigate embankment for animal burrows and fill in any burrow holes with impervious material.

The following additional actions are recommended:


1. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months.
2. Consider providing additional low level outlet facilities to decrease the drawdown time.


c. O & M Procedures

The owner should develop, within one (1) year after formal approval of the report, written operating procedures and a periodic maintenance plan to insure the safety of the dam.

PLATES

**GREEN TURTLE POND DAM  
WEST MILFORD TWP.  
PASSAIC COUNTY, N. J.**






Scale in Feet (Approx.)

2,000 0 2,000 4,000 6,000 8,000 10,000

VICINITY MAP

PLATE IA




LEGEND:

PRE-CAMBRIAN  
gh Hornblende Granite & Gneiss

GEOLOGIC MAP  
GREEN TURTLE POND DAM


1




PLAN

101.7

2



PROFILE






0


1  
2

Existing Top of Dam


3

PROFILE





PROFILE



TYPICAL SECTION

2 + 50

STEEL PLATE DETAIL

FILE

REMARKS OF THE  
AND BY JAMES H. HENRY  
SUPERVISOR OF THE DISTRICT

APPROVED *Mark*  
*George H. H.*  
DISTRICT ENGINEER

FILE

APPLICATION NO.

5

PROFILE



LOCATION PLAN

FILE

DEPARTMENT OF CONSERVATION  
AND RECREATION DEVELOPMENT  
DIVISION OF WATER POWER AND CIVIL

APPROVED March 20, 1937

George B. Mankie

DESIGNATION No. 500

PLANS OF  
AWOSTING DAM SITE  
(GREEN TURTLE POND DAM)

EARTH CONSTRUCTION

WEST MILFORD TWP

PASSAIC COUNTY - NEW JERSEY

DESIGNED 1936


S. A. F. A. S. H. B. N.

WALDO RUDE & ASSOCIATES  
ENGINEERS & LAND SURVEYORS  
ROCKY HILL, CONN. U. S. A.


FILE APPLICATION No.

PLATE 3


1





SECTION B-B




Note:  
UPPER LINE, AS INSTALLED  
LOWER LINE, PROPOSED IMPROVEMENT



— SPI





1000



SECRET

*existing surface*

*Top of E.P. Cap, braced to a smooth surface.*

4

0

— SPILLWAY CHANNEL PROFILE —

SPILLING LAKE

(GREEN TURTLE HOND DAM)



5



10

\_\_\_\_\_

SECRET

\_\_\_\_\_

\_\_\_\_\_

**DATE RECEIVED**

100

APPENDIX A

CHECK LIST - VISUAL OBSERVATIONS

CHECK LIST - ENGINEERING, CONSTRUCTION  
MAINTENANCE DATA

CHECK LIST  
VISUAL INSPECTION  
PHASE 1

Name Dam GREEN TURTLE POND DAM County Passaic State New Jersey Coordinators NJ-DEP

Date(s) Inspection November 16, 1979 Weather Clear Temperature 34°F

Pool Elevation at Time of Inspection 576.3 NGVD Tailwater at Time of Inspection 546.0 NGVD

Inspection Personnel:

Chuck Chin  
Henry King (Recorder)  
Thomas Lakovich

Owner/Representative - None attended

# CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SEEPAGE OR LEAKAGE N/A		
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS N/A		
DRAINS N/A		
WATER PASSAGES N/A		
FOUNDATIONS N/A		

# CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES N/A		
STRUCTURAL CRACKING N/A		
VERTICAL AND HORIZONTAL ALIGNMENT N/A		
MONOLITH JOINTS N/A		
CONSTRUCTION JOINTS N/A		

# EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SURFACE CRACKS None noticed.		
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE None observed.		
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES None.		
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST Good.		
RIPRAP FAILURES None.		

# EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
EARTH EMBANKMENT	Numerous trees, small to large size, growing on both sides of earth embankment. A few trees were uprooted leaving cavities on the downstream slope.	Remove trees and fill cavities.
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Good.	
ANY NOTICEABLE SEEPAGE	Minor seepage was visible at two locations: 1. Approximately 100 feet from the spillway, 5 feet left of the channel. 2. Five feet right of the low level outlet drain.	Clear all vegetation from these two areas and monitor seepage for clearness and flow quantity.
STAFF GAGE AND RECORDER	None.	
DRAINS	None.	

# OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN STILLING BASIN	Could not see stilling basin because of sediment.	Clean out stilling basin.
INTAKE STRUCTURE	Low level outlet drain under water in lake. Not visible.	
OUTLET STRUCTURE	An 18-inch cast iron pipe was observed exiting on the downstream side of the embankment at the channel pool. Pool was filled with sediment to 3/4 level of pipe. No low level outlet gate was found on the embankment.	Clean out pool and pipe. Locate low level outlet gate and check to see if operable.
OUTLET FACILITIES	None.	
EMERGENCY GATE	None.	



# UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
<p>CONCRETE WEIR</p> <p>The concrete spillway appears in good condition.</p>		
<p>APPROACH CHANNEL</p> <p>A long concrete apron, in good condition, serves as approach channel. Trees, vegetation and silt clutter this approach.</p>		<p>Clean out.</p>
<p>DISCHARGE CHANNEL</p> <p>Discharge flows over silted concrete apron and then into a grouted riprap discharge channel. The grout is cracked in some areas.</p>		<p>Repair cracks.</p>
<p>BRIDGE AND PIERS</p> <p>None.</p>		

# GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CONCRETE SILL N/A		
APPROACH CHANNEL N/A		
DISCHARGE CHANNEL N/A		
BRIDGE AND PIERS N/A		
GATES AND OPERATION EQUIPMENT N/A		

# INSTRUMENTATION

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
MONUMENTATION/SURVEYS None.		
OBSERVATION WELLS None.		
WEIRS None.		
PIEZOMETERS None.		
OTHER None.		

# RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SLOPES	Earth slopes and rock outcropping encompass the reservoir. Earth slopes are moderate and stable while rock slopes are steep and firm.	
SEDIMENTATION	None noticed.	

# DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	The bottom of the downstream channel is grouted riprap. It in good condition. The grout has some cracks in it. There are some fallen trees, vegetation and debris in the channel. The channel flow runs into a pool that is located approximately 230 feet from the spillway.	Repair cracks in grout. Remove fallen trees, vegetation and debris.
SLOPES	Shallow to moderate. In good condition.	
APPROXIMATE NUMBER OF HOMES AND POPULATION	There are three homes on the left bank, beyond Greenwood Lake Turnpike, located approximately 1,300 feet from the spillway.	

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	Available on microfilm at N.J. Department of Environmental Protection, (NJ-DEP), 1474 Prospect Street, P. O. Box CN-029, Trenton, NJ 08625.
REGIONAL VICINITY MAP	Available-Passaic County Map and USGS Quadrangle Sheet for Greenwood Lake, New York-New Jersey.
CONSTRUCTION HISTORY	No formal history exists, but can be deduced from available micro-film at NJ-DEP.
TYPICAL SECTIONS OF DAM	Available on microfilm at NJ-DEP.
HYDROLOGIC/HYDRAULIC DATA	Limited Hydrologic data and hydraulic data available on microfilm at NJ-DEP.
OUTLETS - PLAN	Available on microfilm (NJ-DEP)
- DETAILS	Available on microfilm (NJ-DEP)
- CONSTRAINTS	None.
- DISCHARGE RATINGS	Not available.
RAINFALL / RESERVOIR RECORDS	Not available.

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
(continued)

ITEM	REMARKS
DESIGN REPORTS	None available.
GEOLOGY REPORTS	Available USGS Geologic overlay sheet for Passaic County and Engineering Soil Survey of New Jersey. Report No. 3--Passaic County, by Rutgers University. (New Brunswick, N.J.)
DESIGN COMPUTATIONS	} Limited hydrological and hydraulic data.
HYDROLOGY & HYDRAULICS	
DAM STABILITY	
SEEPAGE STUDIES	
MATERIALS INVESTIGATIONS	} Grain size, unit weight and permeability tests of core material are available on microfilm. It is not clear if tested material was used at dam site.
BORING RECORDS	
LABORATORY	
FIELD	
POST-CONSTRUCTION SURVEYS OF DAM	None.
BORROW SOURCES	Unknown.
SPILLWAY PLAN - SECTIONS	} Available on microfilm at NJ-DEP.
- DETAILS	

CHECK LIST  
ENGINEERING DATA  
DESIGN, CONSTRUCTION, OPERATION  
(continued)

ITEM	REMARKS
OPERATING EQUIPMENT PLANS AND DETAILS	None available.
MONITORING SYSTEMS	None available.
MODIFICATIONS	None known to exist.
HIGH POOL RECORDS	Not kept.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None known to exist.
PRIOR ACCIDENTS OF FAILURE OF DAM - DESCRIPTION - REPORTS	None known to exist.
MAINTENANCE OPERATION RECORDS	None known to exist.



APPENDIX B

PHOTOGRAPHS

(Taken on November 16, 1979)

GREEN TURTLE POND DAM



Photo 1 - View of earth embankment looking toward earth spillway and Awosting Road. Reservoir is out of photo to viewer's right. Note numerous trees on slopes of embankment.



Photo 2 - Detail showing spalling in right abutment of spillway.

GREEN TURTLE POND DAM




Photo 3 - View of left abutment and earth embankment. Portion of reservoir is at left. Note trees on slopes of embankment.



Photo 4 - Detail showing vertical crack, located at spillway, in left abutment.

GREEN TURTLE POND DAM



Photo 5 - View of reservoir from earth embankment.  
Spillway is out of photo on viewer's left.



Photo 6 - View of the approach channel to the spillway.  
Portion of earth embankment is at left.

GREEN TURTLE POND DAM



Photo 7 - View of downstream channel looking toward spillway.




Photo 8 - View of spillway looking toward left abutment.

GREEN TURTLE POND DAM



Photo 9 - View of downstream channel from spillway.  
Note vegetation and fallen trees.



Photo 10 - View of low-level outlet drain (18-inch cast  
iron pipe) at lower right showing sedimenta-  
tion in drain.

APPENDIX C

SUMMARY OF ENGINEERING DATA

CHECK LIST  
HYDROLOGIC AND HYDRAULIC DATA  
ENGINEERING DATA

Name of Dam: GREEN TURTLE POND DAM

Drainage Area Characteristics: 0.5 square miles

Elevation Top Normal Pool (Storage Capacity): 576 NGVD(251 acre-feet)

Elevation Top Flood Control Pool (Storage Capacity): N/A

Elevation Maximum Design Pool: 579.76 NGVD(SDF pool: 377 acre-feet)

Elevation Top Dam: 580 NGVD(386 acre-feet)

SPILLWAY CREST:

a. Elevation 576 NGVD

b. Type Broad crest weir with concrete notch

c. Width 1 foot

d. Length 30 feet

e. Location Spillover Entire length of spillway

f. No. and Type of Gates None

OUTLET WORKS:

a. Type 18-inch C.I.P.

b. Location 400 feet left of spillway

c. Entrance Inverts 548 NGVD (estimated)

d. Exit Inverts 546 NGVD (estimated)

e. Emergency Draindown Facilities Gate valve 18-inch dia. C.I.P.

HYDROMETEOROLOGICAL GAGES:

a. Type None

b. Location None


c. Records None

MAXIMUM NON-DAMAGING DISCHARGE: 744 cfs at elevation 580 NGVD



APPENDIX D

HYDROLOGIC COMPUTATIONS



2,000 0 2,000 4,000

Scale: 1" = 2,000 FT.

GREEN TURTLE POND DAM  
DRAINAGE BASIN

PRC Harris, Inc.  
CONSULTING ENGINEERS  
Phase I  
Group XVII

SUBJECT N.J. DAM SAFETY INSPECTION  
GREEN TURTLE POND DAM  
COMPUTED BY S.L.C. CHECKED BY R/L  
GREEN TURTLE POND DAM

SHEET NO. 1 OF 6  
JOB NO. 10-ABZ-01  
DATE 1-7-80

### SIZE CLASSIFICATION

Surface area of Main impoundment	38.57 Acres
Average depth of Lake	19.52 ft
Structural Height of Dam	35 ft
Size Classification	Small

### HAZARD POTENTIAL CLASSIFICATION

Heavily Travelled Roadway and Houses at D/S of Dam	
Hazard Potential	High
Recommended SDF	1/2 PMF

### HYDROLOGIC ANALYSIS

Flooding Routing will be computed by HEC-1 DB using SCS  
Triangular Unit Hydrograph with Curvilinear Transformation  
D.A. = 0.50 SQ. mi.

### PRECIPITATION

From Fig. 15 (Ref.: "DESIGN OF SMALL DAM"), the Drainage  
Area located at the boundary between Zone I & Zone G.  
Probable Max. Precipitation = 25" for 6 HRS. duration & 10 mi<sup>2</sup>.

PRC Harris, Inc.  
CONSULTING ENGINEERS

SUBJECT N.J. DAM SAFETY INSPECTION  
GREEN TURTLE POND DAM  
COMPUTED BY C.L.C. CHECKED BY 12/1

SHEET No. 2 OF 6  
JOB No. 10-AB3-01  
DATE 1-7-80

Duration

% of PMF

	<u>Zone 1</u>	<u>Zone 6</u>	<u>AVG. Value</u>	
6	99	100	99.5	Values are reduced by 20% to account for Misalignment of basin & storm isohyets.
12	111	109	110	
24	119	117	118	
48	127	126	126.5	

INFILTRATION DATA

Drainage Area consists of MMG only

Hydrologic Soil Group

%

Use initial infiltration

0.7 inch

Use Constant infiltration

0.07 in/hr.

Ref. 'Engineering Soil Survey of N.J. Report 3, Passaic County'  
by Rutgers University.

PRC Harris, Inc.  
CONSULTING ENGINEERS

SUBJECT N.J. DAM SAFETY INSPECTION  
GREEN TURTLE POND DAM  
COMPUTED BY C.L.C. CHECKED BY R.L.

SHEET NO. 3 OF 6  
JOB NO. 10-AB3-01  
DATE 1-7-80

TIME OF CONCENTRATION

- 1)  $T_c$  Estimated From Velocity & Water Course length

	Slope %	Velocity (fps)	
Overland Flow	$\frac{820-680}{2200} = 6.4\%$	2.0	upper watershed Wooded Land

$$t_c = \left( \frac{2200}{2.0} \right) / 3600 = 0.31 \text{ hr}$$

- 2) From Nomograph "Design of Small Dam" (p. 71)

$$\Delta L = 820 - 680 = 140'$$

$$L = 2200$$

$$s = 140/2200 = 6.4\%$$

$$t_c = 0.13 \text{ Hr.}$$

- 3) Using FAA Formula For Surface Flow (Airport Drainage)

$$T_c = \frac{1.8(1.1-C)\sqrt{D}}{\sqrt[3]{S}} = \frac{1.8(.8)\sqrt{2200}}{\sqrt[3]{64}(60)} = 0.61 \text{ Hr.}$$

$$\text{Use } T_c = 0.35 \text{ HRS.}$$

$$\text{LAG} = 0.6 \times 0.35 = 0.21 \text{ HRS.}$$

PRC Harris, Inc.  
CONSULTING ENGINEERS

SUBJECT N.J. DAM SAFETY INSPECTION  
GREEN TURTLE POND DAM  
COMPUTED BY CLC CHECKED BY DK

SHEET NO. 4 OF 6  
JOB NO. 10-AB3-01  
DATE 1-8-80



### ELEVATION - AREA - CAPACITY RELATIONSHIP

Information Obtained From U.S.G.S. Map

Elev.	550 *	580	600	620	640
Surface Area (Ac)	0	38.6	58.8	90.0	100.40

\* Estimated bottom elevation of Lake at Spillway


HEC-1 DB PROGRAM will develop storage capacity from  
surface area and elevation.




PRC Harris, Inc.  
CONSULTING ENGINEERS

SUBJECT W Dam safety insp  
Green Turtle Pond Dam  
COMPUTED BY RK CHECKED BY C.L.C.

SHEET NO. 5 OF 6  
JOB NO. 10-A83-01  
DATE 1/8/80



PLAN



SECTION A-A


Ave.  $C_1 = 3.1$  Assume Broad Crest Weir with Breadth = 1'

ref. table 5-3 King & Brater

Ave.  $C_2 = 2.75$  losses due to roughness on the top of dam

ref. HEC-2 user manual

## Drawdown Time Computation



Normal elevation to start draining  
C 576

D.A. = 0.5 sf/m<sup>2</sup>

Inflow = 2 cfs/sq mi = 1.0 cfs

Use Fig. B-8 for CRP discharge

Res. Ele	Area ac/ft	Ave area AC	Vol A-C	AW RES EL	$\frac{h}{D}$	$\frac{Q}{Q_{outlet}}$	$t_1$ hrs time of drawdown $\frac{Vol \times 2.4}{1.97 Q}$	cul time hr	time to drawdown 2.0 dm $\frac{t_1}{2}$	cul time $t_2$ hrs
576	29.0	23.0	138.3	573.137	40.0	41.9	41.9	41.9	1.1	93.0
570	17.1	13.35	66.75	567.5	10.0	34.0	23.8	65.7	0.7	67.5
565	9.6	6.95	34.75	562.5	6.7	28.0	15.0	80.7	0.5	83.0
560	4.3	2.68	13.4	557.5	3.1	17.0	9.6	90.3	0.6	93.2
555	1.05	0.65	1.69	553.7	0.87	5.0	9.1	94.4	9.8	98.1
552.4	0.25									

A) Time of Complete drawdown with no inflow = 94.9 hrs  $\approx$  4 days

B) Time of complete drawdown with inflow = 98.1 hrs = 4 days

(  $A_1 \approx \frac{A_2}{\left(\frac{h}{H_T} + 1\right)^2}$  )  $h + H_T = 30'$   $A_2 = 38.6$  ac. between 580 to 550 NGVD



N J DAM SAFETY INSPECTION PROGRAM---GROUP XVII 10AB301  
N J 00190 GREEN TUTTLE POND, PASSAIC COUNTY, NJ  
MULT RATIO ROUTING, PRC-HARRIS INC., WOODBRIDGE, N J

A1	0	6	0	0	0	4
A2	300					
A3	5	1				
B	1	3	2	1	0	1
C	5	4				
D	0					
E	0					
F	0					
G	0					
H	0					
I	0					
J	0					
K	0					
L	0					
M	0					
N	0					
O	0					
P	0					
Q	0					
R	0					
S	0					
T	0					
U	0					
V	0					
W	0					
X	0					
Y	0					
Z	0					
AA	0					
AB	0					
AC	0					
AD	0					
AE	0					
AF	0					
AG	0					
AH	0					
AI	0					
AJ	0					
AK	0					
AL	0					
AM	0					
AN	0					
AO	0					
AP	0					
AQ	0					
AR	0					
AS	0					
AT	0					
AU	0					
AV	0					
AW	0					
AX	0					
AY	0					
AZ	0					
BA	0					
BB	0					
BC	0					
BD	0					
BE	0					
BF	0					
BG	0					
BH	0					
BI	0					
BJ	0					
BK	0					
BL	0					
BM	0					
BN	0					
BO	0					
BP	0					
BQ	0					
BR	0					
BS	0					
BT	0					
BU	0					
BV	0					
BW	0					
BX	0					
BY	0					
BZ	0					
CA	0					
CB	0					
CC	0					
CD	0					
CE	0					
CF	0					
CG	0					
CH	0					
CI	0					
CJ	0					
CK	0					
CL	0					
CM	0					
CN	0					
CO	0					
CP	0					
CQ	0					
CR	0					
CS	0					
CT	0					
CU	0					
CV	0					
CW	0					
CX	0					
CY	0					
CZ	0					
DA	0					
DB	0					
DC	0					
DD	0					
DE	0					
DF	0					
DG	0					
DH	0					
DI	0					
DJ	0					
DK	0					
DL	0					
DM	0					
DN	0					
DO	0					
DP	0					
DQ	0					
DR	0					
DS	0					
DT	0					
DU	0					
DV	0					
DW	0					
DX	0					
DY	0					
DZ	0					
EA	0					
EB	0					
EC	0					
ED	0					
EE	0					
EF	0					
EG	0					
EH	0					
EI	0					
EJ	0					
EK	0					
EL	0					
EM	0					
EN	0					
EO	0					
EP	0					
EQ	0					
ER	0					
ES	0					
ET	0					
EU	0					
EV	0					
EW	0					
EX	0					
EY	0					
EZ	0					
FA	0					
FB	0					
FC	0					
FD	0					
FE	0					
FF	0					
FG	0					
FH	0					
FI	0					
FJ	0					
FK	0					
FL	0					
FM	0					
FN	0					
FO	0					
FP	0					
FQ	0					
FR	0					
FS	0					
FT	0					
FU	0					
FV	0					
FW	0					
FX	0					
FY	0					
FZ	0					
GA	0					
GB	0					
GC	0					
GD	0					
GE	0					
GF	0					
GG	0					
GH	0					
GI	0					
GJ	0					
GK	0					
GL	0					
GM	0					
GN	0					
GO	0					
GP	0					
GQ	0					
GR	0					
GS	0					
GT	0					
GU	0					
GV	0					
GW	0					
GX	0					
GY	0					
GZ	0					
HA	0					
HB	0					
HC	0					
HD	0					
HE	0					
HF	0					
HG	0					
HH	0					
HI	0					
HJ	0					
HK	0					
HL	0					
HM	0					
HN	0					
HO	0					
HP	0					
HQ	0					
HR	0					
HS	0					
HT	0					
HU	0					
HV	0					
HW	0					
HX	0					
HY	0					
HZ	0					
IA	0					
IB	0					
IC	0					
ID	0					
IE	0					
IF	0					
IG	0					
IH	0					
II	0					
IJ	0					
IK	0					
IL	0					
IM	0					
IN	0					
IO	0					
IP	0					
IQ	0					
IR	0					
IS	0					
IT	0					
IU	0					
IV	0					
IW	0					
IX	0					
IY	0					
IZ	0					
JA	0					
JB	0					
JC	0					
JD	0					
JE	0					
JF	0					
JG	0					
JH	0					
JI	0					
JK	0					
JL	0					
JM	0					
JN	0					
JO	0					
JP	0					
JQ	0					
JR	0					
JS	0					
JT	0					
JU	0					
JV	0					
JW	0					
JX	0					
JY	0					
JZ	0					
KA	0					
KB	0					
KC	0					
KD	0					
KE	0					
KF	0					
KG	0					
KH	0					
KI	0					
KJ	0					
KK	0					
KL	0					
KM	0					
KN	0					
KO	0					
KP	0					
KQ	0					
KR	0					
KS	0					
KT	0					
KU	0					
KV	0					
KW	0					
KX	0					
KY	0					
KZ	0					
LA	0					
LB	0					
LC	0					
LD	0					
LE	0					
LF	0					
LG	0					
LH	0					
LI	0					
LJ	0					
LK	0					
LL	0					
LM	0					
LN	0					
LO	0					
LP	0					
LQ	0					
LR	0					
LS	0					
LT	0					
LU	0					
LV	0					
LW	0					
LX	0					
LY	0					
LZ	0					
MA	0					

N J DAM SAFETY INSPECTION PROGRAM---GROUP XVII 10A8301  
 N J 00190 GREEN TUTTLE POND, PASSAIC COUNTY, NJ  
 MULT RATIO ROUTING, PRC-HARRIS INC., WOODBRIDGE, N J

JOB SPECIFICATION									
NQ	NHR	NNIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
300	0	6	0	0	0	0	0	4	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED

RTIOS= 50 40 30 20 10  
 NPLAN= 1 NRTIO= 5 LRTIO= 1

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH THROUGH GREEN TUTTLE POND

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JFRT	INAME	ISTAGE	IAUTO
LAKE	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	2	50	0.00	50	80	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	25.00	99.50	110.00	118.00	0.00	0.00	0.00

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CHSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	.70	.07	0.00	0.00

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= 21

RECESSION DATA

STRTO= -1.00 QRCNSN= -.05 RTIOR= 2.00

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

UNIT HYDROGRAPH 12 END OF PERIOD ORIGINATES, TC= 0.00 HOURS, LAU= .21 VOL= 1.00  
 271. 833. 891. 590. 296. 162. 87. 46. 25. 13.  
 8. 4.

0		PM F		END-OF-PERIOD FLOW		PERIOD		RAIN		EXCS		LOSS		COMP Q	
MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q		
1.01	06	1	.01	0.00	.01	0.	1.01	15.06	151	30	30	.01	941.		
1.01	12	2	.01	0.00	.01	0.	1.01	15.12	152	38	37	.01	945.		
1.01	18	3	.01	0.00	.01	0.	1.01	15.18	153	45	45	.01	1052.		
1.01	24	4	.01	0.00	.01	0.	1.01	15.24	154	60	60	.01	1226.		
1.01	30	5	.01	0.00	.01	0.	1.01	15.30	155	1.36	1.35	.01	1670.		
1.01	36	6	.01	0.00	.01	0.	1.01	15.36	156	2.42	2.41	.01	2790.		
1.01	42	7	.01	0.00	.01	0.	1.01	15.42	157	76	75	.01	4019.		
1.01	48	8	.01	0.00	.01	0.	1.01	15.48	158	60	60	.01	4044.		
1.01	54	9	.01	0.00	.01	0.	1.01	15.54	159	38	37	.01	3257.		
1.01	1.00	10	.01	0.00	.01	0.	1.01	16.00	160	30	30	.01	2387.		
1.01	1.06	11	.01	0.00	.01	0.	1.01	16.06	161	28	27	.01	1781.		
1.01	1.12	12	.01	0.00	.01	0.	1.01	16.12	162	28	27	.01	1376.		
1.01	1.18	13	.01	0.00	.01	0.	1.01	16.18	163	28	27	.01	1145.		
1.01	1.24	14	.01	0.00	.01	0.	1.01	16.24	164	28	27	.01	1019.		
1.01	1.30	15	.01	0.00	.01	0.	1.01	16.30	165	28	27	.01	953.		
1.01	1.36	16	.01	0.00	.01	0.	1.01	16.36	166	28	27	.01	917.		
1.01	1.42	17	.01	0.00	.01	0.	1.01	16.42	167	28	27	.01	895.		
1.01	1.48	18	.01	0.00	.01	0.	1.01	16.48	168	28	27	.01	882.		
1.01	1.54	19	.01	0.00	.01	0.	1.01	16.54	169	28	27	.01	878.		
1.01	2.00	20	.01	0.00	.01	0.	1.01	17.00	170	28	27	.01	876.		
1.01	2.06	21	.01	0.00	.01	0.	1.01	17.06	171	22	21	.01	860.		
1.01	2.12	22	.01	0.00	.01	0.	1.01	17.12	172	22	21	.01	810.		
1.01	2.18	23	.01	0.00	.01	0.	1.01	17.18	173	22	21	.01	757.		
1.01	2.24	24	.01	0.00	.01	0.	1.01	17.24	174	22	21	.01	722.		
1.01	2.30	25	.01	0.00	.01	0.	1.01	17.30	175	22	21	.01	704.		
1.01	2.36	26	.01	0.00	.01	0.	1.01	17.36	176	22	21	.01	694.		
1.01	2.42	27	.01	0.00	.01	0.	1.01	17.42	177	22	21	.01	689.		
1.01	2.48	28	.01	0.00	.01	0.	1.01	17.48	178	22	21	.01	686.		
1.01	2.54	29	.01	0.00	.01	0.	1.01	17.54	179	22	21	.01	685.		
1.01	3.00	30	.01	0.00	.01	0.	1.01	18.00	180	22	21	.01	684.		
1.01	3.06	31	.01	0.00	.01	0.	1.01	18.06	181	02	01	.01	629.		
1.01	3.12	32	.01	0.00	.01	0.	1.01	18.12	182	02	01	.01	459.		
1.01	3.18	33	.01	0.00	.01	0.	1.01	18.18	183	02	01	.01	279.		
1.01	3.24	34	.01	0.00	.01	0.	1.01	18.24	184	02	01	.01	197.		
1.01	3.30	35	.01	0.00	.01	0.	1.01	18.30	185	02	01	.01	184.		
1.01	3.36	36	.01	0.00	.01	0.	1.01	18.36	186	02	01	.01	172.		
1.01	3.42	37	.01	0.00	.01	0.	1.01	18.42	187	02	01	.01	160.		
1.01	3.48	38	.01	0.00	.01	0.	1.01	18.48	188	02	01	.01	150.		
1.01	3.54	39	.01	0.00	.01	0.	1.01	18.54	189	02	01	.01	140.		
1.01	4.00	40	.01	0.00	.01	0.	1.01	19.00	190	02	01	.01	130.		
1.01	4.06	41	.01	0.00	.01	0.	1.01	19.06	191	02	01	.01	121.		
1.01	4.12	42	.01	0.00	.01	0.	1.01	19.12	192	02	01	.01	113.		
1.01	4.18	43	.01	0.00	.01	0.	1.01	19.18	193	02	01	.01	106.		
1.01	4.24	44	.01	0.00	.01	0.	1.01	19.24	194	02	01	.01	99.		
1.01	4.30	45	.01	0.00	.01	0.	1.01	19.30	195	02	01	.01	92.		
1.01	4.36	46	.01	0.00	.01	0.	1.01	19.36	196	02	01	.01	86.		
1.01	4.42	47	.01	0.00	.01	0.	1.01	19.42	197	02	01	.01	80.		
1.01	4.48	48	.01	0.00	.01	0.	1.01	19.48	198	02	01	.01	75.		
1.01	4.54	49	.01	0.00	.01	0.	1.01	19.54	199	02	01	.01	70.		
1.01	5.00	50	.01	0.00	.01	0.	1.01	20.00	200	02	01	.01	65.		

1.01	5.06	51	01	0.00	01	0.	1.01	20.06	201	02	01	01	61.
1.01	5.12	52	01	0.00	01	0.	1.01	20.12	202	02	01	01	57.
1.01	5.18	53	01	0.00	01	0.	1.01	20.18	203	02	01	01	53.
1.01	5.24	54	01	0.00	01	0.	1.01	20.24	204	02	01	01	49.
1.01	5.30	55	01	0.00	01	0.	1.01	20.30	205	02	01	01	46.
1.01	5.36	56	01	0.00	01	0.	1.01	20.36	206	02	01	01	43.
1.01	5.42	57	01	0.00	01	0.	1.01	20.42	207	02	01	01	40.
1.01	5.48	58	01	0.00	01	0.	1.01	20.48	208	02	01	01	37.
1.01	5.54	59	01	0.00	01	0.	1.01	20.54	209	02	01	01	35.
1.01	6.00	60	01	0.00	01	0.	1.01	21.00	210	02	01	01	33.
1.01	6.06	61	04	0.00	04	0.	1.01	21.06	211	02	01	01	30.
1.01	6.12	62	04	03	01	14.	1.01	21.12	212	02	01	01	29.
1.01	6.18	63	04	03	01	38.	1.01	21.18	213	02	01	01	29.
1.01	6.24	64	04	03	01	75.	1.01	21.24	214	02	01	01	29.
1.01	6.30	65	04	03	01	82.	1.01	21.30	215	02	01	01	29.
1.01	6.36	66	04	03	01	86.	1.01	21.36	216	02	01	01	29.
1.01	6.42	67	04	03	01	88.	1.01	21.42	217	02	01	01	29.
1.01	6.48	68	04	03	01	89.	1.01	21.48	218	02	01	01	29.
1.01	6.54	69	04	03	01	90.	1.01	21.54	219	02	01	01	29.
1.01	7.00	70	04	03	01	90.	1.01	22.00	220	02	01	01	29.
1.01	7.06	71	04	03	01	90.	1.01	22.06	221	02	01	01	29.
1.01	7.12	72	04	03	01	90.	1.01	22.12	222	02	01	01	29.
1.01	7.18	73	04	03	01	90.	1.01	22.18	223	02	01	01	29.
1.01	7.24	74	04	03	01	90.	1.01	22.24	224	02	01	01	29.
1.01	7.30	75	04	03	01	90.	1.01	22.30	225	02	01	01	29.
1.01	7.36	76	04	03	01	90.	1.01	22.36	226	02	01	01	29.
1.01	7.42	77	04	03	01	90.	1.01	22.42	227	02	01	01	29.
1.01	7.48	78	04	03	01	90.	1.01	22.48	228	02	01	01	29.
1.01	7.54	79	04	03	01	90.	1.01	22.54	229	02	01	01	29.
1.01	8.00	80	04	03	01	90.	1.01	23.00	230	02	01	01	29.
1.01	8.06	81	04	03	01	90.	1.01	23.06	231	02	01	01	29.
1.01	8.12	82	04	03	01	90.	1.01	23.12	232	02	01	01	29.
1.01	8.18	83	04	03	01	90.	1.01	23.18	233	02	01	01	29.
1.01	8.24	84	04	03	01	90.	1.01	23.24	234	02	01	01	29.
1.01	8.30	85	04	03	01	90.	1.01	23.30	235	02	01	01	29.
1.01	8.36	86	04	03	01	90.	1.01	23.36	236	02	01	01	29.
1.01	8.42	87	04	03	01	90.	1.01	23.42	237	02	01	01	29.
1.01	8.48	88	04	03	01	90.	1.01	23.48	238	02	01	01	29.
1.01	8.54	89	04	03	01	90.	1.01	23.54	239	02	01	01	29.
1.01	9.00	90	04	03	01	90.	1.02	0.00	240	02	01	01	29.
1.01	9.06	91	04	03	01	90.	1.02	0.06	241	00	0.00	0.00	27.
1.01	9.12	92	04	03	01	90.	1.02	0.12	242	00	0.00	0.00	25.
1.01	9.18	93	04	03	01	90.	1.02	0.18	243	00	0.00	0.00	24.
1.01	9.24	94	04	03	01	90.	1.02	0.24	244	00	0.00	0.00	22.
1.01	9.30	95	04	03	01	90.	1.02	0.30	245	00	0.00	0.00	21.
1.01	9.36	96	04	03	01	90.	1.02	0.36	246	00	0.00	0.00	19.
1.01	9.42	97	04	03	01	90.	1.02	0.42	247	00	0.00	0.00	18.
1.01	9.48	98	04	03	01	90.	1.02	0.48	248	00	0.00	0.00	17.
1.01	9.54	99	04	03	01	90.	1.02	0.54	249	00	0.00	0.00	16.
1.01	10.00	100	04	03	01	90.	1.02	1.00	250	00	0.00	0.00	15.
1.01	10.06	101	04	03	01	90.	1.02	1.06	251	00	0.00	0.00	14.
1.01	10.12	102	04	03	01	90.	1.02	1.12	252	00	0.00	0.00	13.
1.01	10.18	103	04	03	01	90.	1.02	1.18	253	00	0.00	0.00	12.
1.01	10.24	104	04	03	01	90.	1.02	1.24	254	00	0.00	0.00	11.
1.01	10.30	105	04	03	01	90.	1.02	1.30	255	00	0.00	0.00	10.
1.01	10.36	106	04	03	01	90.	1.02	1.36	256	00	0.00	0.00	10.
1.01	10.42	107	04	03	01	90.	1.02	1.42	257	00	0.00	0.00	9.
1.01	10.48	108	04	03	01	90.	1.02	1.48	258	00	0.00	0.00	8.
1.01	10.54	109	04	03	01	90.	1.02	1.54	259	00	0.00	0.00	8.
1.01	11.00	110	04	03	01	90.	1.02	2.00	260	00	0.00	0.00	7.

111	03	01	90	1.02	2.06	261	0.00	0.00	0.00	7
111	04	01	90	1.02	2.12	262	0.00	0.00	0.00	6
111	03	01	90	1.02	2.18	263	0.00	0.00	0.00	6
114	04	01	90	1.02	2.24	264	0.00	0.00	0.00	5
115	04	01	90	1.02	2.30	265	0.00	0.00	0.00	5
116	04	01	90	1.02	2.36	266	0.00	0.00	0.00	5
117	04	01	90	1.02	2.42	267	0.00	0.00	0.00	4
118	04	01	90	1.02	2.48	268	0.00	0.00	0.00	4
119	04	01	90	1.02	2.54	269	0.00	0.00	0.00	4
120	04	01	90	1.02	3.00	270	0.00	0.00	0.00	4
121	20	01	135	1.02	3.06	271	0.00	0.00	0.00	3
122	20	01	271	1.02	3.12	272	0.00	0.00	0.00	3
123	20	01	418	1.02	3.18	273	0.00	0.00	0.00	3
124	20	01	514	1.02	3.24	274	0.00	0.00	0.00	3
125	20	01	563	1.02	3.30	275	0.00	0.00	0.00	3
126	20	01	589	1.02	3.36	276	0.00	0.00	0.00	2
127	20	01	604	1.02	3.42	277	0.00	0.00	0.00	2
128	20	01	611	1.02	3.48	278	0.00	0.00	0.00	2
129	20	01	615	1.02	3.54	279	0.00	0.00	0.00	2
130	20	01	617	1.02	4.00	280	0.00	0.00	0.00	2
131	24	01	629	1.02	4.06	281	0.00	0.00	0.00	2
132	24	01	663	1.02	4.12	282	0.00	0.00	0.00	2
133	24	01	699	1.02	4.18	283	0.00	0.00	0.00	1
134	24	01	722	1.02	4.24	284	0.00	0.00	0.00	1
135	24	01	734	1.02	4.30	285	0.00	0.00	0.00	1
136	24	01	740	1.02	4.36	286	0.00	0.00	0.00	1
137	24	01	744	1.02	4.42	287	0.00	0.00	0.00	1
138	24	01	746	1.02	4.48	288	0.00	0.00	0.00	1
139	24	01	747	1.02	4.54	289	0.00	0.00	0.00	1
140	24	01	747	1.02	5.00	290	0.00	0.00	0.00	1
141	30	01	764	1.02	5.06	291	0.00	0.00	0.00	1
142	29	01	814	1.02	5.12	292	0.00	0.00	0.00	1
143	29	01	867	1.02	5.18	293	0.00	0.00	0.00	1
144	30	01	902	1.02	5.24	294	0.00	0.00	0.00	1
145	30	01	920	1.02	5.30	295	0.00	0.00	0.00	1
146	30	01	929	1.02	5.36	296	0.00	0.00	0.00	1
147	30	01	934	1.02	5.42	297	0.00	0.00	0.00	1
148	30	01	937	1.02	5.48	298	0.00	0.00	0.00	1
149	30	01	939	1.02	5.54	299	0.00	0.00	0.00	0
150	30	01	939	1.02	6.00	300	0.00	0.00	0.00	0

SUM 23.60 21.65 1.95 71585.  
( 599. ) ( 550. ) ( 49. ) ( 2027.06 )

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
4044.	1034.	298.	239.	71600.
115.	29.	8.	7.	2027.
	19.23	22.20	22.20	22.20
	488.53	563.87	563.92	563.92
	513.	592.	592.	592.
	632.	730.	730.	730.

UFS  
CHS  
INCHES  
MM  
AC-FT  
THOUS CU M

## HYDROGRAPH ROUTING

## ROUTING DISCHARGE THROUGH DAM

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTABE	IAUTO
DAM	1	0	0	0	0	1	0	0
ROUTING DATA								
QLOSS	CLOSS	AVG	IRRES	ISAME	IDPT	IPMP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
NSTPS NSTOL								
1	0	LAG	ANSKK	X	TSK	STORA	ISPRAT	
		0	0.000	0.000	0.000	-576.	0	

SURFACE AREA=

90. 100.

CAPACITY=

2830. 4733.

ELEVATION=

620. 640.

CREL	SPWID	COOM	EXPW	ELEV	COOL	CAREA	EXPL
576.0	30.0	3.1	1.5	0.0	0.0	0.0	0.0

## DAM DATA

TOPEL	COOD	EXPD	DAMWID
580.0	2.8	1.5	275.

PEAK OUTFLOW IS 679. AT TIME 16.20 HOURS

PEAK OUTFLOW IS 525. AT TIME 16.20 HOURS

PEAK OUTFLOW IS 375. AT TIME 16.30 HOURS

PEAK OUTFLOW IS 231. AT TIME 16.30 HOURS

PEAK OUTFLOW IS 98. AT TIME 16.50 HOURS

\*\*\*\*\*

\*\*\*\*\*



